

State Geological Survey
KANSAS DRILLERS LOG
 WICHITA, BRANCH


S. 24 T. 32 R. 10 E
 W

API No. 15 — 007 — 20,348
 County Number

Loc. NW SE NW

County Barber

640 Acres
 N



Locate well correctly

Elev.: Gr. 1,441

DF 1,446 KB 1,449

Operator
Barnett Oil, Inc.

Address
1625 Vickers KSB&T Building Wichita, Kansas 67202

Well No. #1 Lease Name Moses

Footage Location
 feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Ambercrombie Drilling, Inc Geologist Alfred W. Stude

Spud Date 8/29/75 Total Depth 4,370' P.B.T.D. _____

Date Completed 9/6/75 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12½"	8 5/8"		242'	Common	225	2% gel, 3% c.c.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval(s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Barnett Oil, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Dry Hole

Well No. 1 Lease Name Moses

S 24 T 32 S R 10 W

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Shale & Shells	0	240	Herington	1614 (- 165)
Shale	240	760	Winfield	1672 (- 223)
Shale & Shells	760	1540	Towanda	1736 (- 287)
Shale	1540	1955	Ft. Riley	1790 (- 341)
Shale & Shells	1955	2745	Florence	1832 (- 383)
Shale & Lime	2745	4025	Council Grove	1984 (- 535)
Lime & Shale	4025	4344	Cottonwood	2152 (- 703)
Lime	4344	4370	Neva	2192 (- 743)
			Indian Cave	
			(Sand Stone)	2422 (- 973)
			Wabaunsee	2464 (-1015)
			Tarkio	2598 (-1149)
			Howard	2856 (-1407)
			Topeka	3078 (-1629)
			Elgin Sand	3268 (-1819)
			Heebner	3398 (-1949)
			Toronto	3412 (-1963)
			Douglas	3444 (-1995)
			Lansing	3622 (-2173)
			Kansas City	3904 (-2455)
			B/Kansas City	4121 (-2672)
			Maraton	4190 (-2741)
			Mississippian	4332 (-2883)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



G. Gould
 G. Gould Signature
 President Title
 10/10/75 Date

CONTRACTOR'S WELL LOG

OPERATOR:	Barnett Oil, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	MOSES #1
LOCATION:	NW SE NW Section 24-32S-10W Barber County, Kansas
GEOLOGIST:	Alfred Stude
SPUD DATE:	August 29, 1975
COMPLETION DATE:	September 6, 1975

0	240	Shale & Shells
240	760	Shale
760	1540	Shale & Shells
1540	1955	Shale
1955	2745	Shale & Shells
2745	4025	Shale & Lime
4025	4344	Lime & Shale
4344	4370	Lime
	4370	Rotary Total Depth

Drilled 240' of 12 1/4" surface hole. Ran 5 jts. 8 5/8" surface casing, Set @ 240'. Cemented with 245 .. 3% ca.cl. 2% gel. Cement Circulated. Plug was down @ 7:00 a.m. August 29, 1975.
 Ran 141 jts. of 4 1/2" casing. Set @ 4363' with 125 sx. cement. 12% salt 2% gel. Plug was down @ 10:00 p.m. September 6, 1975.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the MOSES #1, NW SE NW, Section 24-32S-10W, Barber County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 8th day of September, 1975.



Sandra Russell
 Sandra Russell - Notary Public

Commission Expires: July 21, 1979