

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GLOBE OIL & REFINING CO. & B. M. HEATH
Farm- Goemann No. 1

SEC. 29 T. 32 R. 10W
NW NE NW

Total Depth. 4965'

Comm. 3-25-55

Comp. 4-30-55


Shot or Treated.

Contractor. Dudley & Heath Drlg. Co.

Issued. 6-18-55

County Barber

KANSAS



Elevation. 1461' DF

CASING:
8 5/8" 280' cem w/300 sx
5 1/2" 4504.81' cem w/100 sx

Production. Est. Flow 25 BO &
10 BWPD

Figures indicate Bottom of Formations.

surface	435
red bed	1160
red bed, shale, shells & lime	1410
shale & lime shells	1615
lime	1742
shale & lime	1818
lime	1902
Anhydrite and shale	1984
lime and shale	2024
lime, shale & sand	2162
lime and shale	2303
shaly lime	2360
shale, lime & sand	2567
sandy lime & shale	2763
sandy lime	2866
shale, sandy lime	3033
sandy lime	3172
sandy lime & shale	3265
lime, shale, sandy	3338
shale & lime	3555
shale, lime & sand	3617
sandy lime	3665
sand	3698
shale, lime & sand	3785
lime	3848
lime & shale	3925
lime	3970
lime & shale	4025
sandy	4040
lime	4142
lime & shale	4224
lime	4274
lime & shale	4484
sand	4489
shale & lime	4415
chat lime	4426
lime	4470
lime & chat	4504
lime	4552
Mississippi lime	4575
lime	4800
lime & dolomite	4808
sandy lime & shale	4834
sand, lime & shale	4846
sandy shale	4893
sandy lime & shale	4920
chat	4932
lime	4965
Total Depth	

Tops:	
Elgin Zone	3320
Base Oread	3568
First Douglas Sand	3590
Second Douglas Sand	3658
Lansing	3696
Mississippi Chert	4404
Mississippi Lime	4483
Kinderhook	4600
Chattanooga	4652
Viola	4692
Simpson Shale	4776
Simpson Sand	4794
Arbuckle	4918
Schlumberger T.D.	4964

Perforated 25/4438-4433
Acidized 250 gal. mud and 250 gal. wash acid.
Squeezed
Perforated 12/4433-4436
Perforated Wellex Bazooka Gun 1 shot 4434
1 shot 4436
1 shot 4439
1 shot 4440

Acidized 300 gal. mud acid
Acidized 250 gal. mud acid
Dowell fraced w/2500# and 190 bbls.