


WELL COMPLETION REPORT AND DRILLER'S LOG

PI No. 15 — 007 — 20684
County Number

S. 29 T. 32 R. 10 ^{XX} W
Loc. N/2 NE/4 SE/4
County Barber

Operator: MOLZ OIL CO.
Address: Rt. 2 Box 54, Kiowa, Kansas 67070
Well No. 1 Lease Name Traffas
Footage Location: 330 feet from (N) line 660 feet from (E) line East of SE/4
Principal Contractor: Sweetman Drilling, Ins. Geologist: Gordon W. Keen
Spud Date: 10/29/78 Date Completed: 12/6/78 Total Depth: 4444' P.B.T.D.: 4444'
Directional Deviation: less than 1 degree Oil and/or Gas Purchaser: Panhandle Eastern



640 Acres
Locate well correctly
Elev.: Gr. 1466
DF 1473 KB 1476

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	25 lbs.	240'	Common	225	
Production	7 7/8 ths	4 1/2"	10.5	4444 KB	common	150	5% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval
none			none		

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8 ths	4442	none

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acid Howco 250 gal. reg. 15%, and 250 gal. HF acid	4440-4444
Frac. 5500# sand & 7000 gal. 2% KCL water	

INITIAL PRODUCTION

Date of first production: 12/6/78 Producing method (flowing, pumping, gas lift, etc.): Flowing
 RATE OF PRODUCTION PER 24 HOURS: Oil 60 bbls. Gas 1,100 MCF Water none bbls. Gas-oil ratio 18,333/1 CFPB
 Disposition of gas (vented, used on lease or sold): Vented Producing interval (s): 4440-4444 Open Hole

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
MOLZ OIL CO.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
GAS

Well No. 1
Lease Name
Traffas

S 29 T 32 R 10 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>Chert- White, tan, gray, fresh, sharp, to tripolitic. Very good porosity & free oil stain.</p> <p>DST #1 Packer failed</p> <p>DST#2 4406-44 Op. 30" SI 30" Op. 30" SI 30" GTS 8" Rec. 180' Gas cut drilling mud 10" Ga. 77,000 cfgpd 25" Ga. 159,000 cfgpd IF 78-100# ISIP 1544# FF 100-100# FSIP 1544#</p> <p>NO ELECTRIC LOGS RUN</p>	4436	4444	Mississippi	4436

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received



Signature

Title

10-7-79

Date