

Douglas H. McGinness
PETROLEUM GEOLOGIST
Res. (316) 838-8070

MCGINNESS & MCGINNESS
CONSULTING GEOLOGISTS
150 N. MAIN • SUITE 1026
WICHITA, KANSAS 67202
(316) 267-6065 • FAX (316) 269-2517

Douglas H. McGinness, II
PETROLEUM GEOLOGIST
Res. (316) 687-4873

ORIGINAL

RECEIVED

OCT 09 2001

KCC WICHITA

Molz Oil Company
(OWWO) #1 Cekosky
E/2 NE NW 35-32S-10W
Barber County, Kansas

8 5/8 @332'/225 sx
OTD @ 4410'
5 1/2" @ 4706'
RTD @ 4707'


Spud: 6/29/2001
Comp: (Drlg) 7/7/2001
Elevation: 1426 GL, 1434 RB

All tops & zones of porosity and staining were measured from Rotary Bushing.

	<u>SPL</u>	<u>EL Log</u>
Mississippi	4380' (-2946')	4372' (-2938')
Kinderhook	4603' (-3169')	4601' (-3167')
Viola	4687' (-3253')	-----
RTD	4707' (-3273')	4650' (-3216')

The drilling time was not available for recording until 4516'. A show of oil and gas was evidenced in the drilling samples in the Upper portion of the Mississippi section. No Mizener Sand was encountered and the Viola was void of any porosity or staining in the top section. It was recommended that casing be set 1 ft. off bottom and the Mississippi perforated from 4390'-4402' and treated as necessary to obtain commercial oil and gas production.

Sincerely,



Douglas H. McGinness
Geologist