

KAN-EX, INC. - DAILY DRILLING REPORT

LEASE: #1 Eckhardt	PROSPECT: Eckhardt	ELEVATION 1530 GR
SPOT: Approx. 2,200' FEL & 1,390' FNL	SECTION: 8-32S-10W	1543 KB
COUNTY: Barber	STATE: Kansas	
CONTRACTOR: Eagle Drilling, Inc.	TOPS: Indian Cave 2522 (-979)	
GEOLOGIST: Mike Spain & Grant Gardner	Elgin Sd 3424 (-1881)	
MIRT: June 6, 1981	Heebner 3552 (-2009)	
	Lansing 3718 (-2175)	
	Stark 4136 (-2513)	
SURFACE CASING: Ran 9 joints of new 24lb 8-5/8" surface casing.	Kinderhook 4614 (-3071)	
Set at 303', cemented with common cement 3% calcium chloride,		
2% jell, cement did circulate. Cemented by Sun Company.		

<u>DATE</u>	<u>REPORT</u>
6-6-81	Moved in - rigged up and spud at 9:45 P.M.
6-7-81	Ran 9 joints 24lb 8-5/8" surface casing (new)
6-8-81	Drilling at 1,650'. Mud weight 9.3, Vis. 29
6-9-81	Drilling ahead at 2,430' Mud weight 9.2, Vis. 35 DST #1 (Indian Cave) 2510 - 2598 Strong blow throughout test 30-60-45-90, Recovered 2024' SW IHP 1239# FHP 1207# ISIP 1049# FSIP 1038# FP 452-985/879-1038# TEMP 118°
6-10-81	Drilling at 2,800' Mud weight 9.2, Vis. 35
6-11-81	Drilling ahead at 3,606'
6-12-81	Drilling ahead at 4,115' Mud Weight 9.2 Vis. 37 DST #2 (Swope & Hertha) 4135-4205 30-60-45-90, Recovered 180' watery cut mud, 560' SW IHP 2007# FHP 2017# ISIP 1666# FSIP 1666# FP 39-313/323-401# TEMP 115°
6-13-81	Drilling ahead at 4,220' Mud Weight 9.2 Vis. 43 DST #3 (Cherokee) 4367-4396 First open weak blow, 30-30-30-30, Recovered 6' mud IHP 2133# FHP 2114# ISIP 49# FSIP 39# FP 39-39-39-39# TEMP 115°
6-14-81	Drilling ahead at 4,401' Mud Weight 9.2 Vis. 44 DST #4 (Mississippi) 4385-4432 First open weak blow to start, died after 8 minutes Second open weak blow throughout test 30-30-45-30, Recovered 20' mud IHP 2114# FHP 2124# ISIP 98# FSIP 90#
6-15-81	Drilling ahead at 4,447' Mud Weight 9.2 Vis. 55 DST #5 (Mississippi) 4430-4447 30-30-45-90, Recovered 60' mud, trace of oil IHP 2182# FHP 2124# ISIP 1385# FSIP 1064# IFP -plugged off FFP 4969# TEMP 115°
6-16-81	Drilling ahead at 4,640' Mud Weight 9.2 Vis. 48

DATEREPORT

6-17-81 Drilling ahead at 4,781' Mud Weight 9.1 Vis. 50
Preparing to run DST #6 (Simpson)

6-18-81 4,811' and logging


6-19-81 DST #6 (Simpson) 4752 - 4781
30-60-30-10 Recovered 3" Mud
IHP 2381[#] FHP 2260[#] ISIP 49[#] FSIP 49[#]
IFP 49-49[#] FFP 49-49[#] Temp 120^o

Plugged and Abandoned

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Barber County. Sec. 8 Twp. 32S Rge. 10 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE/4

Lease Owner Kan-Ex, Inc.
Lease Name ECKHARDT Well No. 1

Office Address 800 Bitting Building
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 06-19 1981
Application for plugging filed 06-19 1981
Application for plugging approved 06-19 1981
Plugging commenced 06-19 1981
Plugging completed 06-19 1981

Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4798
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	303	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

plugged at 8:00 p.m. on 06-19-81 with common cement. 60 sacks 700' 50 sacks at 300'
10 sacks 40' 5 sacks mouse hole and 5 sacks rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor


STATE OF Kansas COUNTY OF Sedgwick, ss.

(employee of owner) or (owner or operator)
the above-described well, being first duly sworn on oath, says: That I have knowledge of
facts, statements, and matters herein contained and the log of the above-described well
filed and that the same are true and correct. So help me God.

(Signature) Robert L. Eisel

SUBSCRIBED AND SWORN TO before me this 29 day of June, 1981 (Address)

commission expires 12 May 1985
Carolyn G. Sloderbeck
Notary Public.
Carol G. Sloderbeck



RECEIVED
JUL 6 - 1981

VINCENT OIL CORP.