

5-32-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BEARDMORE DRILLING CO.  
Farm- Jones No. 1

SEC. 5 T. 32 R. 11W  
NW NW NW

Total Depth. 4326  
Comm. 3-7-52 Comp. 3-20-52  
Shot or Treated.  
Contractor. Beardmore Drilling Co.  
Issued. 2-14-53

County Barber  
KANSAS



CASING:

8 5/8 150' w/ 100 sx cement

Elevation. 1518 DF

Production. Dry

Figures indicate Bottom of Formations.

red rock & shale	70
shale & shells	1280
lime & shale	1680
broken lime	2465
shale & shells	2735
lime & shale	3255
broken lime	3325
lime & shale	3385
sand	3480
lime & shale	3740
lime	4294
lime & chert	4300
lime	4326
Total Depth	

SCOUT-TOPS:

Elgin sand	3375
Lansing	3702
Mississippi	4290

DST #1: rec. 10' mud BHP 1110# no gas  
3375-85

DST #2: 4288-94 open 1 hr. rec. 25'  
mud BHP 300#

DST #3: 4294-4302 open 1 hr. rec. 30'  
mud. BHP 85# 20 min.

DST #4: 4299-4326 rec. 630' GC mud  
960' water shut 1/2 hr BHP 750#  
FFP 650#