

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Plotted

5-32-11W

Company - H. W. SKINNER
Farm - H. W. Skinner No. 1

SEC. 5 T. 32 R. 11W
NE SW NE

Total Depth. 4406' PB 4343½'
Comm. 10-21-46 Comp. 1-25-47
Shot or Treated.
Contractor.
Issued. 4-5-47

County. Barber
KANSAS



Elevation. 1562 *rh*

CASING:

10-3/4" 182' Cem.
5-3/16" 4339' Cem. w/250 s

Production. Temporarily Abandoned

Figures Indicate Bottom of Formations.

red bed & shells	50
red bed	254
red bed, gyp & shells	430
red bed & shells	655
red bed & shale	805
shale & shells	1100
salt & shale	1275
shale & gyp & shells	1490
shale & shells	2375
shale	2775
shale & lime	2870
shale & shells	2940
lime	3000
lime & shale	3440
sand	3444
shale	3483
lime & shale	3600
lime	3608
sand	3620
lime sdy	3630
lime	3666
lime & shale	3725
lime	3760
lime & shale	3790
lime	4268
shale & lime	4332
lime	4337
chat RTD	4350
chat	4385½
chert	4406

Total Depth (Cable)

P.B. 4360' 1-27-47

P.B. 4343½' 1-30-47 Drilled
out to 4345½'

16 hr test fill up 160' fluid
10 a.m. to 1 a.m. made 27 gal.
fluid 3 gal. oil rest water.
Dumped 2 bbls acid down casing.
Run 5' wtr out of tank on top.

2-3-47 Swabbed hole dry before 500
gal. acid had 200' oil or swabbed
bailed 30' wtr.

2-4-47 Swabbing very little oil.

2-6-47 600' fluid in hole testing
16 hrs, taking 2 hr. test. Got
75' on swab.

2-20-47 6 Bailers Wtr. Run swab .
Got about 100' oil 30' wtr.

Tops:

Topeka	3160
Elgin Sand	3429
Lansing	3750
Miss.	4337