

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-32-11W

Company- LARIO OIL & GAS COMPANY
Farm- John Regnier No. 1
becomes 'Swayden 1'

SEC. 6 T. 32 R. 11W
NW 1/4 NW
(NW NE NW)

Total Depth. 4647'
Comm. 1-8-60 Comp. 1-26-60
Shot or Treated.
Contractor, Prime Drilling Co.
Issued. 3-26-60

County Barber
KANSAS



CASING:
8 5/8" 238' cem. w/200 sx.

Elevation. 1502 RB

Production. Dry

Figures Indicate Bottom of Formations.

sand	20
red bed	760
shale	1270
anhydrite	1315
shale & shells	1550
lime & shale	2500
shale & lime	2700
lime & shale	2980
lime	3200
lime & shale	3345
lime	3357
lime & sand	3475
lime & shale	3548
lime, sand & shale	3565
sand & shale	3696
lime	4280
cherty lime	4321
lime	4347
lime, shale & chert	4377
lime & chert	4399
lime	4440
lime & shale	4485
shale & lime	4509
lime	4623
sand	4647RTD
Total Depth	

TOPS: GEOLOGICAL	
Anhydrite	1270
Elgin Sandstone Zone	3335
Hoebner	3467
Douglas Sand Zone	3487
Clean Douglas Sand	3560
Lansing	3695
Mississippi Chat	4254
Mississippi Lime	4317
Kinderhook	4387
Viola	4512
Simpson	4603
Simpson Sand	4614