

CONFIDENTIAL11-3211103
KCC
p(

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

RICKE "A" #1 Compt. KCC

SIDE ONE TITE HOLE, FILING ONE ORIGINAL

(Rules 82-3-130 and 82-3-107)

DOCKET NO. NP

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F XX Letter requesting confidentiality attached.

C ☒ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run_____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5171 EXPIRATION DATE 6/30/84

OPERATOR TXO Prod. Corp. API NO. 15-007-21,705

ADDRESS 200 W. Douglas, Suite 300 COUNTY Barber
Wichita, KS 67202 FIELD McGuire

** CONTACT PERSON Harold R. Trapp PROD. FORMATION dry
PHONE 265-9441 no Indicate if new pay.

PURCHASER dry hole-never produced LEASE Ricke

ADDRESS dry hole-never produced WELL NO. "A" #1

DRILLING Aldebaran. Rig #3 1980 Ft. from North Line and

CONTRACTOR 453 S. Webb Rd., Ste. 100 Box 18611 660 Ft. from East Line of (E)
Wichita, KS 67207 the NE (Qtr.) SEC 11 TWP 32S RGE 11 (W).

PLUGGING Sun Oil Well Cementing (Office Use Only)

CONTRACTOR P.O. Box 169 KCC

ADDRESS Great Bend, KS 67530 KCS ☒

TOTAL DEPTH 3820' PBTD none SWD/REP

SPUD DATE 11-12-83 DATE COMPLETED D&A, 11-18-83 PLG.

ELEV: GR 1542 DF 1548 KB 1551 NGPA

DRILLED WITH (CABLE) (ROTARY) (HYD) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE none

Amount of surface pipe set and cemented 8-5/8" @ 315' DV Tool Used? no

RELEASED

Date: DEC 1 1984

FROM CONFIDENTIAL

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion. Other completion. NGPA filing.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

I, Harold R. Trapp, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

State Geological Survey
WICHITA BRANCH

Side TWO

OPERATOR

TXO PROD. CORP.

LEASE NAME Ricke

SEC 11

TWP 32S

RGE

11

(X)

(W)

FILL IN WELL INFORMATION AS REQUIRED;

WELL NO "A" #1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
Check if no Drill Stem Tests Run. XX Check if samples sent Geological Survey. DST #1, 3612-90' (Douglas), w/results as follows: IFP/30": 67-201#, good blow ISIP/60": 1333# FFP/45": 241-322#, good blow FSIP/90": 1333# Rec: 90' O&WCM (35% wtr, 15% gas, 45% mud, & 5% oil) + 510' MW (CH1=70,000 ppm)			LOG TOPS Herington 1776 Onaga Sh 2595 -1044 Wabaunsee 2647 -1096 Stotler 2801 -1250 Topeka 3066 -1515 Elgin Sh 3427 -1876 Heebner 3611 -2060 Toronto 3667 -2116 Lansing 3778 -2227 RTD 3820 LTD 3818	
If additional space is needed use Page 2				

TITE HOLE

Report of all strings set—surface, intermediate, production, etc.

CASING RECORD (New) or XXXXX

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8-5/8"	24#	315'	common	250	3% CaCl & 2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none	none	none	none	none	none
TUBING RECORD					
Size	Setting depth	Packer set at			
none	none	none			