

13-32-11W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

MUSGROVE PETROLEUM CORPORATION &
Company- GULF OIL CORPORATION
Farm- Minnie McGuire No. 1

SEC. 13 T. 32 R. 11W
C E/2 SE

Total Depth. 4500 PBTD 4485
Comm. 12-11-56 Comp. 2-8-57
Shot or Treated.
Contractor. Lewis Drilling Co.
Issued. 7-13-57

County Barber
KANSAS



CASING:
8 5/8 @ 200' w/ 200 sx cmt.
5 1/2 @ 4499' w/ 150 sx cmt.

Elevation. 1502 DF

Production. 2,010,000 CFGPD

Figures indicate Bottom of Formations.

red bed & shale 1580
lime & shale 3590
lime 4245
lime & shale 4380
lime & chert 4448
lime 4500
Total Depth

Plugged back to 4485

TOPS:
Heebner 3545
Douglas shale 3613
Douglas sand 3664
Lansing 3727
Penn. sand (scout) 4385
Basal Conglomerate 4400
Reworked Mississippi 4414
Mississippi chert 4423
Mississippi lime 4427

Perf. 24/4412-20, Perf/ 6/4420-22
500 gal acid, failed, Perf. 6/4422-24
would not take acid, Reperf 24/4412-24