

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
500 East Murdock, Wichita, Kansas


14-32-11W

Company - BEARDMORE-BARBARA  
Farm - Stewart "C" No. 1

SEC. 14 T. 32 R. 11W  
SW SW SW

Total Depth. 4915  
Comm. 5-14-56 Comp. 5-29-56  
Shot or Treated.  
Contractor. Beardmore Drilling Co.  
Issued. 7-28-56

County Barber KANSAS



Elevation. 1510 DF

Production. 130 BOPD

CASING:

8 5/8" 183' cem w/120 sx. Circ.  
5 1/2" 3667' cem w/75 sx.

Figures Indicate Bottom of Formations.

cellar	5
sand	80
red rock, shale	183
shale	955
salte	1475
shale, shells	1555
shale, lime	3830
lime	3991
lime, shale	4400
lime	4435
lime, shale	4630
lime	4775
sand	4787
sand, shale	4830
lime	4915
Total Depth	

Tops :	
Lansing	3741
Ero. Mississippi	4387
Ero. Miss. Limestone	4432
Kinderhook	4564
Viola	4669
Simpson shale	4744
Simpson sand	4760
Arbuckle	4868

DST #1 3579-3605 Shut in 15 min.,  
ope 1 hr., shut in 15 min., gas to  
surf. in 12 min. (40,000 in 15 min.  
and 80,000 at end of hr.) Recovered  
30' gas cut mud, 60' gas cut mud  
w/oil specks, 60' heavily oil & gas  
cut mud, 60' oily mud, t0' muddy  
oi. IF 100#, FF 225#, IBHP 1365#  
FBHP 1370#.

RTD 4915  
CTD 3587