

18-32-11W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BEARDMORE DRLG. CO.
Farm- Gilbert No. 1

SEC. 18 T. 32 R. .11W
C SW SE

Total Depth. 4340'
Comm. 8-6-64 Comp. 8-18-64
Shot or Treated.
Contractor. Sierra Petroleum Co.
Issued. 1-9-65

County Barber
KANSAS



Elevation. 1450' KB

Production. GA 874 MCFGPD, SIP

CASINO:

8 5/8" 209' cem. w/165 sx.
4 3/8" 3639' cem. w/75 sx.

Figures indicate Bottom of Formations.

Soil & Sand	40
Shale & Shells	170
Shale	209
Red Bed	700
Shale & Shells	1612
Lime & Shale	2355
Shale & Shells	2620
Shale & Lime	3435
Lime, Shale & Sand	3535
Shale & Lime	3740
Lime	4285
Lime & Chert	4315
Chert	4340
Rotary Total Depth	

SAMPLE TOPS

E-LOG TOPS

Lecompton	3289	3286
Elgin Shale	3329	3324
Heebner	3493	3490
Snyderville Sandstone	3508	3506
U UP. Douglas Sandstone	3565	3564
Lo. " "	3610	3610
Lansing-Kansas City	3690	3687
Base Kansas City	4175	4172
Basal PPennsylvanian		
sandstone	4289	4286
Mississippi Chert	4299	4297
Total Depth	4340	4339