

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


22-32-11W

Company- BEARDMORE-BARBARA
Farm- Schnelle No. 1

SEC. 22 T. 32 R. 11W
C SW SE

Total Depth. 4910
Comm. 10-5-56 Comp. 10-23-56
Shot or Treated.
Contractor. Beardmore Drilg Co.
Issued. 11-17-56

County Barber
KANSAS



CASING:
8 5/8" 180' cem w/120 sx.

Elevation. 1507 D.F.

Production. Dry

Figures indicate Bottom of Formations.

cellar	5
sand, shale	30
red rock, shale, shells	180
shale, shells	1500
shale, lime	2325
shale	2560
shale, lime	3589
shale, lime, sand	3685
shale	3791
lime	3960
shale, lime	4025
lime	4125
shale, lime	4190
lime	4230
shale, lime	4335
lime	4595
shale, lime	4645
lime	4690
shale, lime	4725
sand	4773
sand, shale	4820
shale, lime	4895
lime	4910

Total Depth

Tops:	
Heebner	3573
Lansing	3751
Drum	4038
Base Kansas City	4228
Marion	4256
Cherokee	4372
Mississippi	4417
Kinderhook	4547
Chattanooga	4617
Viola	4656
Simpson shale	4728
Simpson sand	4733
Arbuckle	4865

- #4 4648-65 Shut in 15 min., weak blow for 9 mins. than died, open 30 mins., shut in 15 mins., rec. 10' mud. IBHP 28, FBHP 28, IF 12, FF 12, Hydrostatic press 2495.
- #5 4729-38 Shut in 15 min., open 1 hr, good blow throughout, shut in 15 min., rec. 500' gassy salt wtr., 3190' salt wtr, IBHP 2280, FBHP 1850, IF 180 FF 1740.

Drill Stem Tests:

- #1 3674-85 Shut in 15 min., open 50 min. good blow shut in 15 " rec. 1950' salt wtr. IBHP failed. FBHP 1365#, IF 340#, FF 975#, Hydrostatic press. 1940#, temp. 126.
- #2 4118-4458 Shut in 15 min., weak blow for 25 min. then died, open 45 mins. shut in 15 min., rec. 26' mud. IBHP 55#, FBHP 95#, IF 28#, FF 32#, Hydrostatic press. 2495#.
- #3 4468-4525 Shut in 15 min., had weak blow for 27 min., then died, open 40 min., shut in 15 min., rec. 30' mud. IBHP 109, FBHP 40, IF 28, FF 28, Hydrostatic press. 2418.