

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

24-32-11W

508 East Murdock,

Wichita, Kansas

Company- MAGNOLIA-STANOLIND

Farm- Ryser-McGuire No. 1

SEC. 24 T. 32 R. 11W
SE NW SE

Total Depth. 4505'


Comm. 11-23-56

Comp. 12-21-56

Shot or Treated.

Contractor. Bass Drlg. Co.

Issued. 2-23-57

County Barber
KANSAS

Elevation. 1494'

Production. Calc. OF 11,890,000
CFGPD

Figures indicate Bottom of Formations.

red bed-sand	279
red bed-shale	726
shale-anhydrite	1577
anhydrite-lime	2101
lime-shale	4103
lime	4178
lime-shale	4494
chert-dolomite	4504
Dolomite	4505
Total Depth	

TOPS:

Heebner shale	3558
Lansing-Kansas City	3737
Burgess sand(scout)	4398
Basal Penn. sand	4402
Reworked Mississippi	4415
Mississippi	4436

DST # 4 - 4397-4410, Open 1 hr.,
18 min. Gas in 2 min. Ga. 3,210,000
in 1 min. Ga. 4,720,000 in 50 min.
and stabilized. Rec. 180' GCM, FP
1310# - 1405# in 30 min., SIBHP
1685#.

DST # 1 - 4415-35, Open 1 hr.,
Gas in 1½ min. Ga. 5,110,000
in 8 min., 6,000,000 in 15 min.
and stabilized. Rec. 3' condensate,
FP 1280# - 1445#, 30 min. SIBHP
1670#.

DST # 3 - (straddle pier) 4436-61,
Open 1 hr. Gas in 10 min. Ga.
98,000 CFG in 15 min., 139,000
CFG in 25 min. and stabilized.
Rec. 110' GCM, FP 45 - 70#, 30
min. SIBHP 1650#.

DST # 2 - 4464-4505, Open 1 hr.
Gas in 11 min. w/valve to flow
line opened a crack. Blow died
in 45 min. Rec. hole full of
gas, Rec. 90' GCM, FP 45-55#,
30 min. SIBHP 875#, bldg.