

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


33-32-11W

Company. MAGNOLIA PETROLEUM CO.
Farm. Williams "B" No. 1

SEC. 33 T. 32 R. 11W
SW SW SE

Total Depth. 4530
Comm. 8-19-55 Comp. 9-6-55
Shot or Treated.
Contractor. Harry Bass Drilling Co.
Issued. 12-24-55

County Barber
KANSAS



CASING:
9 5/8 @ 360' w/ 325 sx cmt.

Elevation. 1507 DF

Production. Dry

Figures Indicate Bottom of Formations.

surface hole	70
red bed & sand rock	342
red bed	361
red bed & shale	1250
lime, shale & anhydrite	1568
lime & shale	1674
lime, anhydrite & shale	1850
lime & shale streaks	2004
lime, shale & gypsum	3280
lime & shale	3426
lime, gypsum & shale	3695
lime & sand	3812
lime	4328
lime & shale	4448
Mississippi chat	4465
lime	4484
lime & chat	4509
lime & chert	4530
Total Depth	

TOPS:
Heebner 3610
Douglas sand 3747
Mississippi 4437

DST #1: 4438-65, open 1 hr. SI 20
min. strong bl. thruout, rec. 25'
rotary mud, Fp 32-32#, BHP 630#

DST #2: 4467-4530, open 1 hr. SI 20
min. med-strong bl. rec. 15' rotary
mud, FP 30-30#, BHP 50#