

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


6-32-12W

Company- PRYOR & TRACY
Farm- Wilson No. 1

SEC. 6 T. 32 R. 12W
C NW NW

Total Depth. 4700
Comm. 9-28-55 Comp. 10-21-55
Shot or Treated.
Contractor. D & M Drilling Co., Inc.
Issued. 12-3-55

County Barber
KANSAS



8 5/8 @ CASING 201 w/ 150 sx cmt.

Elevation. 1504 RB

Production. Dry

Figures indicate Bottom of Formations.

shale & sod	15	Simpson shale	4531
sand	35	Simpson sand	4540
shale & sand	201	Arbuckle	4647
red bed & shells	645		
shale, shells & sand	1255		
anhydrite	1277		
shale & shells	1372		
shale & shells w/ lime strks.	1630		
lime & shale streaks	1900		
broken lime	2009		
lime w/ shale streaks	2185		
broken lime	2255		
shale w/ lime streaks	2318		
lime & shale	2468		
sandy shale w/ lime streaks	2779		
shale & lime	2847		
lime w/ shale streaks	2885		
shale w/ lime & sand streaks	3045		
lime w/ shale streaks	3140		
broken lime	3200		
shale & sand w/ lime streaks	3465		
lime w/ shale streaks	3573		
shale & sand	3620		
broken lime & sand	3650		
sand	3666		
lime	3685		
lime w/ shale streaks	3745		
lime	3778		
lime & shale	3894		
lime	4012		
lime w/ shale streaks	4072		
lime & shale	4085		
lime w/ shale streaks	4132		
lime & shale	4185		
lime & shale w/ some chert	4225		
lime & chert	4230		
lime, shale & chert	4257		
shale & chert	4297		
lime & chert streaks	4327		
chert, lime & shale	4348		
lime & shale	4452		
shale & sand	4540		
sand	4594		
lime & shale	4647		
lime	4700		
Total Depth			

TOPS:

Heebner	3485
Toronto	3502
Douglas sand #1	3548
Douglas sand #2	3620
Brown lime	3682 ?
Lansing	3682 ?
Mississippi	4196
Kinderhook	4354
Viola	4452