

11-32-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- HARMS-BURT DRILLING CO.  
Farm- Adams No. 1

SEC. 11 T. 32 R. 12W  
NE NE SW

Total Depth. 4329'  
Comm. 3-24-55 Comp. 4-11-55  
Shot or Treated.  
Contractor.  
Issued. 8-11-56

County Barber KANSAS



Elevation. 1459' RB

Production. Dry

CASING:

8 5/8" 205' cem. w/200 sx. & 5 sx of Cal. Cl.

Figures indicate Bottom of Formations.

sand	45
red bed & shells	205
shale & shells	935
Anhydrite	943
shale & shells	1035
shale & shells & salt	1145
shale & lime	2605
shale w/lime streaks	2785
lime-	2905
lime & shale	3085
lime	3190
lime w/shale streaks	3290
lime & shale	3369
sand & shale	3420
sand, shale & shells	3450
lime & shale	3525
lime & shale streaks	3595
shale	3624
<del>sand</del> shale & sand	3654 3684
lime	3700
lime & shale	3753
lime	4243
Mississippi lime	4249
Chat	4255
lime	4276
Chert	4320
lime & Chert	4329
Total Depth	

TOPS:

Anhydrite	935
Elgin Sand	3360
Douglas Sand	3623
Lansing/Kansas City	3669
Mississippian	4235

DRILL STEM TESTS

- No. 1 3622-3634 open 1 hr. recovered 185' muddy salt wtr. IFP 0 FFP 220#  
BHP 1260#
- No. 2 4234-4243 open 2 hrs. recovered 20' drilling mud. IFP 15# FFP 28#  
BHP 350#
- No. 3 4234-4249 open 2 hrs. gas in 1 1/2 hrs. recovered 120' oil cut mud.  
IFP 15# FFP 48# BHP 638#
- No. 4 4249-4260 open 2 hrs. recovered 12' slightly oil cut mud 50' watery  
mud IFP 15# FFP 28# BHP 160#

RAN ELECTRIC LOG.