

11-32-12W
Smith 'B' 2
Westmore Drilling


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. AYLWARD DRILLING COMPANY
Farm. Smith "C" No. 1

SEC. 11 T. 32 R. 12W
SE SE SE

Total Depth. 4262'
Comm. 10-28-61 Comp. 11-8-61
Shot or Treated.
Contractor.
Issued. 3-31-62

County Barber
KANSAS



Elevation. 1454' DF

Production. 25 BOPD

CASING:

8 5/8" 196' cem w/250 sx.
4 1/2" 4233' cem w/50 sx.

Figures Indicate Bottom of Formations.

sand	35
red rock	350
red bed & shale	800
shale & shells	1470
lime & shale	1829
lime	2190
lime & shale	2315
shale & lime	3035
lime & shale	3257
shale & lime	3510
sand & shale	3668
lime	4262
Total Depth	

TOPS:

Elgin (scout)	3304
Heebner	3488
Douglas (scout)	3496
Lansing	3666
Mississippi	4232

DST 4233-62', op 1 hr, 10 mins, gas to surf. 10 mins TSTM Rec. 725' Fl., 125' OCM, 420' MCO, 175' oil, 5' water. IBHP 1568#/30 mins, FBHP 1538#/45 mins. FP 90#-180#.