

13-32-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO. ET AL
Farm- Smith "B" No. 1

SEC. 13 T. 32 R.12W
SW NW NW

Total Depth. 4260'
Comm. 8-8-61 Comp. 8-18-61
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 12-23-61

County Barber
KANSAS



Elevation. 1452' DF

Production. 88 BOPD

CASING:

8 5/8" 263' cem w/275 sx.
5 1/2" 4236' cem w/50 sx.

Figures Indicate Bottom of Formations.

sand	65
red bed	130
shale, shells & red bed	830
shale, lime & shells	1320
shale & lime	1460
lime & shale	1795
lime	1940
lime & shale	2648
shale & lime	2995
lime & shale	3410
shale & lime	3670
lime	4260
Total Depth	

TOPS:

Elgin	3304
Heebner	3486
Douglas	3494
Lansing	3663
Mississippian	4236

DST 4234-60' op 1 hr, gas in 8 min TSTM.
Rec. 90' GCM, 120' O&GCM, 60' muddy oil
& 60' oil. IBHP 1500#/20 min, FBHP 1260#/30 min.
FP 75#-105#.