

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

14-32-12W

Company- E. H. ADAIR OIL CO. ETAL
Farm- Adams No. 1

SEC. 14 T. 32 R.12W
SE SE NW
450' fr EL & 330' fr SL of NW/4

Total Depth. 4722'


Cement. 3-20-56
Shot or Treated.

Comp. 4-10-56

Contractor. Adair Rig No. 1
Issued. 5-12-56

County Barber

KANSAS



Elevation. 1508' KB

CASING:
8 5/8" 161' cem w/150 sx

Production. Dry

Figures indicate Bottom of Formations

red rock	130
shale & shells	1184
shale & lime	1800
lime	1870
lime & shale	3000
lime	3043
shaley lime	3215
shale	3350
lime	3392
sandy shale	3527
shaley lime	3589
sandy shale	3657
sandy lime	3688
sandy shale	3754
lime	3758
shale	3762
lime	4338
chert	4394
cherty lime	4506
shale	4587
black shale	4623
cherty lime	4704
shale	4709
sand	4722
Total Depth	

Tops: Electric	
Elgin Zone	3391
Heebner	3571
Douglas	3578
Brown Lime	3752
Lansing	3760
Mississippi Chert	4335
Kinderhook	4503
Chattanooga	4585
Viola	4621
Simpson Shale	4702
Simpson Sand	4706