

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

14-32-12W

Company. AYLWARD DRILLING CO. ET AL
Farm. Smith No. 1

SEC. 14 T. 32 R. 12W
NE NE NE

Total Depth. 4650'

Comm. 12-10-59


Shot or Treated.

Contractor.

Issued. 4-30-60

Comp. 12-30-59

County Barber
KANSAS



CASING:

8 5/8" 203' cem. w/225 sx.
5 1/2" 4603' cem. w/125 sx.

Elevation. 1456 RB

Production. 97 BOPD

Figures Indicate Bottom of Formations.

sand	60
red rock	204
red bed & blue shale	665
red bed & shale	900
shale & shells	1140
salt	1200
shale & shells	1450
lime & shale	1475
lime	1790
lime & shale	1910
sandy lime & shale	2030
lime & shale	2135
shale & lime	3320
shale	3490
sand	3562
sandy lime	3575
shale & lime	3670
lime	3900
chalky lime	4015
lime	4080
lime & shale	4191
lime, shale & chert	4240
lime & chert	4260
chert & lime	4290
chert, lime & shale	4324
lime	4342
lime, chert & shale	4381
lime & chert	4402
lime, chert & shale	4415
lime & shale	4506
shale & lime	4535
lime	4607
sand & shale	4613
sand & shale	4650
Total Depth	

Viola	4522
Simpson	4603
RTD	4615
Cable Tool T.D..	4650

DST 4231-60 Open 1 hr. G.T.S. 3",
TSTM Rec. 1000' MOCM, 1000' oil.
IBHP 1620#/20". FBHP 1520#/30".
FP 200#-400#.

DST 4260-90 Open 1 hr. G.T.S. 9",
TSTM. Rec. 90' MC hvy oil. IBHP
1630#/20". FBHP 605#/30". FP
70#-160#.

No log run.

TOPS: GEOLOGICAL

Elgin Zone	3309
Heebner	3484
Douglas	3490
Lansing	3664
Mississippi	4229
Kinderhook	4407