

State Geological Survey

WICHITA BRANCH KANSAS DRILLERS LOG

15-007-20508

API No. 15 — 007 — 20,508
County Number

Operator

George R. Jones

Address

Suite 1310, 125 N. Market Wichita, Kansas 67202

Well No.

#1

Lease Name

Orr

Footage Location

660 feet from (N) line

660 feet from (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Lee Poulsen

Spud Date

6-18-77

Total Depth

4356'

P.B.T.D.

~~4357~~ 4356'

Date Completed

6-27-77


Oil Purchaser

S. 17 T. 32 R. 12 W

Loc. NW NW

County Barber

640 Acres



Locate well correctly

Elev.: Gr. 1598'

DF 1601'

KB 1603'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 3/4"	8 5/8"	20#/236'	242'	Reg. Portland Common	200	2% gel, 3% CC
Production		4 1/2"	10.5#/44'	4334'	HOWCO 60-40 Pozmix	150	2% gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

none - open hole

Size	Setting depth	Packer set at
2 3/8"	4290'	


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500# MCA	4334' - 4356'
14,350 gals. gelled wtr foam(Nitrogen), 6,000 # 20/40 sd,	
8,000# 10/20 sd	

INITIAL PRODUCTION

Date of first production 3-20-78		Producing method (flowing, pumping, gas lift, etc.) ~~pumping~~ <i>flowing</i>			
RATE OF PRODUCTION PER 24 HOURS	Oil <i>none</i> bbls.	Gas 56 MCF	Water <i>1</i> bbls.	Gas-oil ratio — CFPB	
Disposition of gas (vented, used on lease or sold) sold to Cities Service Gas Co.			Producing interval(s) Mississippi		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator George R. Jones		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas	
Well No. #1	Lease Name Orr		
S 17 T32S R12 ~~XX~~ W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Mississippi 30-30-60-60 FP's 62-62 & 62-82# Recovered 130' GCM & 222,000 CFGPD <i>ISIP 289 #</i> <i>FSIP 289 #</i>	4330'	4356'	Heebner 3640' (-2037) Lansing 3809' (-2206) Stark 4177' (-2574) B/K.C. 4240' (-2637) Mississippi 4330' (-2727)
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature s/George R. Jones Operator Title 4-18-78 Date		