

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

19-32-12W


Company-SKELLY OI CO.
Farm-Warren Fee No. 2

SEC. 19 T. 32 R.12W
SW SW SW

330' fr SL, 440' fr WL, SW/4

Total Depth. 4497 PBD 4475
Comm. 5-7-55 Comp. 5-20-55
Shot or Treated Acid. & Sand-Oil-Frac: 500 gals. 4460-75,
Contractor Chas. Hulme Drilling Contractor 1000 gals. 4430-57½
Issued. 7-16-55

County Barber
KANSAS



CASING:
8 5/8 @ 333' w/ 200 sx cmt.
5 1/2 @ 4497' w/ 200 sx cmt.

Elevation. 1633 DF

Production. 791 BOPD

Figures Indicate Bottom of Formations.

clay & red rock	125	Sand Oil Frac No. 1 between 4460-4475'
red bed & shells	333	Sand Oil Frac No. 2 between 4430-4457'
red bed, shale & shells	1100	Sand Oil Frac No. 3 between 4430-4457½'
shale & lime	1740	Sand Oil Frac No. 4 between 4430-4457½'
lime	1900	
sandy lime	2110	Significant Geological Formations:
lime	2255	Mississippi Lime Oil from 4430-4457½'
lime & shale	2400	Oil from 4460-4475'
lime	2455	
shale & shells	2535	
lime & shale	2660	
shale & shells	2995	
lime & shale	3005	
lime	3230	
shale	3250	
lime	3395	
lime & sand	3485	
sand & shale	3645	
shale & lime	3770	
sand & lime	3943	
lime	4016	
sandy lime	4114	
lime	4160	
chalky lime	4185	
lime	4399	
lime & chert	4424	
chert	4490	
chert & lime	4497	
Total Depth		

TOPS:

Heebner	3718
Ireland sand	3730
Lansing	3896
Base KC	4329
Marmaton	4337
Mississippi	4424

DST #1: packer @ 4420, 37' anchor,
open 24 min. gas to surf immed. gauged
2,310 MCFG mud to surf 23 min. oil to
surf. 24 min. flow est. 4 BOPH,
recovery circ. out. IFP 460#, FFP 685#,
BHP 1615#/20 min.

Ran Schlumberger Survey

Producing Formation:
Mississippi Lime 4430' to 4457½'
4460' to 4475'

Shot or Acid Treatment Record:
5-25-55, 500 gals, shot between 4460 and 4475'
Put in by Halliburton

5-26-55, shot between 4460 and 4475', Put in
by Halliburton.

6-1-55, shot between 4430 and 4457½', Put in
by Halliburton.