

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


19-32-12W

Company- SKELLY OIL CO.
Farm- Warren Fee No. 3

SEC. 19 T. 32 R. 12W
SW SE SW
990' fr EL, 330' fr SL, SW/4

Total Depth. 4477 PBD 4470
Comm. 5-29-55 Comp. 6-13-55
Shot or Treated. 500 gal. acid 4407-40, Sand-Oil-Frac 4407-40
Contractor. Chas. Hulme Drilling Co.
Issued. 9-3-55

County Barber
KANSAS



8 5/8 @ CASING: 319' w/ 175 sx cmt.
5 1/2 @ 4477' w/ 200 sx cmt.

Elevation. 1615 DF

Production. 275 BOPD

Figures indicate Bottom of Formations

surface soil & clay	45
sand, gravel, shale & shells	319
red bed & shells	470
shale & shells	1480
lime	1735
sandy lime	1875
lime	2435
shale	2565
shale & lime	2640
shale	3005
shale & lime	3130
lime	3205
sandy lime	3310
lime	3440
lime & shale	3550
lime	3655
lime & sand	3794
lime	3900
lime & shale	3955
lime	4176
cherty lime	4207
lime	4298
lime & shale	4374
lime	4396
chert	4420
chert w/ limey stringers	4428
chert	4477
Total Depth	P.B. 4470

TOPS:	
Heebner	3699
Ireland	3711
Brown lime	3875
Lansing	3882
Base KC	4303
Marmaton lime	4314
Mississippi lime	4398

DST #1: 4389-4436, open 1 hr. gas to
surf. 3 1/2 min. gas gauged 1,500 MCFG,
rec. 50' SOCM, 120' O&GCM, 120' GCMO,
IFP 180#, FFP 280#, BHP 1590#.

DST #2: 4436-77, open 2 hrs: wk. bl.
thruout; rec. 55' drlg. mud, IFP 65#,
FFP 48#, BHP 80#.

Ran Schlumberger Survey

Producing formation Mississippi lime
4407-4440

Oil show 4407-4440