

AUG 23 1969

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

FORSYTH UNIT, TRACT #5, WELL #3
140' SW of SW NE Section 20-32S-12W
Barber County, Kansas

Commenced: May 31, 1969
Completed: June 10, 1969

oil

OPERATOR - Barbara Oil Company

DEPTH	FORMATION	REMARKS
From	To	
0	160	Red rock
160	286	Shale and shells Ran 8 joints of 8-5/8" casing, set @ 286' w/250 sacks cement.
286	934	Red bed and shells
934	1125	Shale
1125	1763	Shale and lime
1763	1860	Shale w/lime streaks
1860	3515	Lime and shale
3515	3628	Shale and lime w/sand
3628	3925	Shale and lime
3925	3946	Lime w/chalk
3946	4318	Lime
4318	4400	Lime and shale
4400	4470	Mississippi
4470	TD	Ran 136 joints of used 5-1/2" casing, set @ 4469' w/150 sacks cement.



I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled 140' SW of SW NE Section 20-32S-12W, Barber County, Kansas to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 13 day of June, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public