

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


23-32-12W

Company- E. H. ADAIR OIL COMPANY
Farm- Bloom No. 1

SEC. 23 T. 32 R. 12W
NE NE NW

Total Depth. 4675
Comm. 12-12-54 Comp. 1-1-55
Shot or Treated.
Contractor. Musgrove Petr. Co.
Issued. 4-23-55

County Barber KANSAS



Elevation. 1504 KB

Production. 67 bbls. oil

CASING:

8 5/8" 172' cem. w/125 sx
5 1/2" 4674' cem. w/100 sx

Figures indicate Bottom of Formations.

redbeds & sand	185	shale limey	4599
redbeds and shells	550	lime cherty	4672
shale & shells	614	sand	4675
redbeds & shale	840	Total depth	
Anhydrite	855		
shale & shells	1280	Tops:	
shale & lime	1530	Elgin zone	3372
lime	1720	Heebner	3535
lime & shale	3009	Douglas	3553
lime	3073	Lansing-KC	3743
shaley lime	3197	Mississippi	4302
shale	3214	Kinderhook	4485
shaley lime	3231	Chattanooga	4562
shale	3327	Viola	4599
shaley lime	3372	Simpson	4672
shale & sdy shale	3492		
lime	3495	DST #1, 3552-70, 1 hour, good	
limy shale	3513	blow, shut in 30 min., rec.	
lime	3519	1000' gas, 30' sl. gas cut mud,	
shale dark	3526	60' sl. gas cut S.W., BHP 975#.	
lime	3535	IFP 0, FFP, 0	
shale blk	3540	DST #2 3670-83, fair blow, 1 hr.	
limy shale	3553	rec. 240' salt water, 1080#.	
shaley sand	3566	BHP in 30 minutes.	
sand	3590	DST #3 4295-4317, open 1 hour	
shaley sand	3677	strong blow, rec. 90' O & GCM,	
sand	3699	150' watery oil cut mud, 30'	
sdv shale	3716	muddy and oily water. BHP, 550#	
shaley sand	3737	in 20 minutes.	
shale dark	3743	DST #4, 4290-4325, open 2 hrs,	
lime	3972	rec. 210' O) & GCM, 60' HO & GCM,	
lime porous	3988	120' muddy and gassy oil, 60' oily	
lime shaley	4010	water. BHP 940# in 30 minutes.	
lime porous	4024	FFP 100#.	
lime	4038		
shale	4042		
lime cherty	4078		
shale	4082		
lime	4114		
shale blk	4117		
lime	4154		
shale	4158		
lime	4176		
shaley lime	4196		
lime	4209		
shaley lime	4285		
lime	4295		
shale	4302		
chert, show oil	4361		
limy chert	4451		
lime	4485		
shale limy	4562		
shale blk	4580		