

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


24-32-12W

Company. *Aurora Gasoline?* AYLWARD DRILLING CO. et al  
Farm. Smith No. 1

SEC. 24 T. 32 R. 12W  
NW NE NW

Total Depth. 4627  
Comm. 9-16-55 Comp. 10-2-55  
Shot or Treated.  
Contractor. Aylward Drilling Co.  
Issued. 12-17-55

County Barber  
KANSAS



CASING:  
8 5/8 134' w/ 125 sx cmt.

Elevation. 1440 DF

Production. Dry

Figures indicate Bottom of Formations.

sand & gravel	30
red rock	74
red rock & shale	519
red bed & shale	1220
salt	1320
anhydrite	1400
shale w/ lime	1560
lime & shale	1740
lime & sand	1850
sand	1880
lime & sand	1985
lime & shale	2145
sand & shale	2280
sandy lime & shale	2745
lime & shale	2865
sandy lime & shale	2980
lime & sand	3121
lime & shale	3330
sand & shale	3698
sand & lime	3764
lime & shale	3890
lime & sand	3932
lime, sand & shale	4016
lime	4103
lime, shale & sand	4172
lime & shale	4286
chert & lime	4328
cherty lime & shale	4350
lime & shale	4399
lime	4420
lime & shale	4580
lime	4623
lime	4627
Total Depth	

RTD

TOPS:	
Heebner	3506
Douglas	3522
Lansing	3694
Mississippi	4266
Kinderhook	4426
Viola	4543
Simpson	4620

DST #1: 4268-86, open 2 hrs. rec.  
30' SGCM, 240' gas, BHP 50#.

DST #2: 4546-50, open 1 1/2 hrs. rec.  
30' GCM, 390' gas, BHP 480#.