

25-32-12W

KANSAS DRILLERS LOG

OCT 18 1972
State Geological Survey
WICHITA, BRANCH

API No. 15 — 007 — 20207
County Number

S. 25 T. 32S R. 12 W
Loc. C NE NE
County Barber

Operator
Beacon Resources Corporation

Address
Suite 1000 Century Plaza Bldg., Wichita, Ks. 67202


Well No. 1 Lease Name **MacGregor**

Footage Location
660 feet from (N) ~~(S)~~ line **660** feet from (E) ~~(W)~~ line

Principal Contractor **Sweetman Drilling Co.** Geologist **Harold Steincamp**

Spud Date **9/14/72** Total Depth **3665** P.B.T.D. **--**

Date Completed **--** Oil Purchaser **--**



Locate well correctly
Elev.: Gr. 1432
DF KB 1441

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4	8-5/8		265	HA5 Poz	50	--

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
--	--	--	--	--	--

Size	Setting depth	Packer set at
--	--	--

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
--	--

INITIAL PRODUCTION

Date of first production **--** Producing method (flowing, pumping, gas lift, etc.) **--**

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	-- bbls.	-- MCF	-- bbls.	-- CFPB

Disposition of gas (vented, used on lease or sold) **--** Producing interval(s) **--**

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Beacon Resources Corporation** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **1** Lease Name **MacGregor** dry hole


S25 T 32S R 12 W

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3497-3545, op 1 hr 15 min wk to fair blow, 180' GIP, 150' OCM, 60' WM 1264-1109#, FP 12-23#, & 47-76#.				
DST #2 3586-3600, op 1 hr 15 min wk blow, 280' SW, FP 9-41#, 62-119# BHP 1086-1043#				
DST #3 3376-3404, op 1 hr 15 min 1600' SW, BHP 1348-1334#, FP 114-485#, 545-1121#				
Log tops: Elgin Sd. 3370 Heebner 3514 Snyder Sd. 3530 Douglas Sand 3586 LTD 3665 RTD 3665				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.




 Signature
 Manager of Production
 Title
 October 10, 1972
 Date