

ACO-1 WELL HISTORY

Compt.

DOCKET NO. 11-10000

3545-52' Perforations

Side TWO

WEL-28

TXO PROD. CORP.

LEASE NAME Randels

SEC 26 TWP 32S RGE 12

(X)
(W)

WELL NO "A" #1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.

Top

Bottom

Name

Depth

Check if no Drill Stem Tests Run.
XX Check if samples sent Geological Survey.

DST #1, 3420-3445' (Elgin), misrun.

DST #2, 3420-45' (Elgin), misrun.

DST #3, 3420-45' (Elgin), w/results as follows:

IFP/30": 82-93#, strong blow

ISIP/60": 921#

FFP/45": 70-82#, GTS in 5", ga 8.7 MCFD

FSIP/90": 1420#

Rec: 125' DM w/OS

DST #4, 3450-65' (Snyderville), w/results as follows:

IFP/30": 82-176#, GTS in 10", Ga 233 incr. to 594 MCFD

ISIP/60": 1442#

FFP/45": 105-199#, Ga 510 incr. to 600 MCFD

FSIP/90": 1442#

Rec: 130' OCM (70% oil)

DST #5, 4005-35' (Drum), w/results as follows:

IFP/30": 93-152#, strong blow

ISIP/60": 1534#

FFP/45": 93-169#

FSIP/90": 1546#

Rec: 410' SW + 930' GIP

DST #6, 4300-4320' (Miss), w/results as follows:

IFP/30": 93-93#, strong blow

ISIP/60": 164#

FFP/45": 93-93#, strong blow FSIP/90": 176# Rec: 50' VSOCM + 30' OCM (35% oil)

If additional space is needed use Page 2

Ran O.H. Logs

Report of all strings set — surface, intermediate, production, etc.

CASING RECORD (New) or (REWORK)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8"	24#	413'	60-40poz lite	350 150	2% CaCl 3% gel
Production		4-1/2"	10.5#	4225'	Class H	100	.75% friction reducer & 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none	none	none	4 JSPF (33 h)	Swope	4122-30'
TUBING RECORD			4 JSPF (17 h)	Lans.	3988-92'
			4 JSPF (25 h)	Lansing A	3726-32'
			4 JSPF (29 h)	Snyderville	3545-52'
Size	Setting depth	Packer set at			
2-3/8"					