

OPERATOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMMENCED: July 15, 1975
15-007-20336 29-32-12W

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202


DRILLING COMPLETED: July 25, 1975

CASING RECORD: 6 Jts. 8 5/8" 256'
cemented with 225 sacks

133 Jts. 4 1/2" 4432'
cemented with 75 sacks

LOCATION: Thomas-Forsyth No. 2
SW NE
Section 29-32S-12W
Barber County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1975
CONSERVATION DIVISION
Wichita, Kansas



0 - 170 Red bed & shale
170 - 1010 Shale
1010 - 1325 Shale & shells
1325 - 1875 Shale
1875 - 2065 Shale & lime
2065 - 2290 Lime, shale & sand
2290 - 2418 Shale
2418 - 2695 Lime & shale
2695 - 2935 Lime, shale & sand
2935 - 3051 Shale & lime
3051 - 3595 Lime & shale
3595 - 3732 Shale & lime
3732 - 4063 Lime & shale
4063 - 4171 Lime
4171 - 4269 Lime & chert
4269 - 4306 Lime & shale
4306 - 4389 Shale & lime
4389 - 4433 Lime
4433 Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

BY Betty Brault
Secretary-Treasurer