

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- PETROLEUM, INC.  
Farm- Warwick No. 1

SEC. <sup>29</sup>~~27~~ T. 32 R. 12W  
NE NW NE

Total Depth. 4515'  
Comm. 1-29-58 Comp. 2-12-58  
Shot or Treated.  
Contractor. Garvey Drlg.  
Issued. 7-4-59

County Barber  
KANSAS



CASING:

8 5/8" 517.09' cem w/325 sx.

Elevation. 1603' DF

Production. Dry

Figures indicate Bottom of Formations.

red bed & shale	170
red bed & gyp	400
red bed & shells	520
red bed	980
shale & shells	1780
lime & shale	2070
lime	2190
shale & lime	3190
lime	3275
lime & shale	3361
shale	3453
sand & shale	3555
shale	3800
shale & lime	3874
lime	4405
lime & chert	4430
chert	4480
lime	4515
Total Depth	

TOPS:

Elgin Zone	3489
Heebner	3670
Douglas	3706
Lansing	3860
Base Kansas City	4297
Mississippian	4410
Mississippi Lime	4504

DST #1 4407-4430', op 1 hr, good blow  
10 min., weak 50 min., rec. 30' drlg.  
mud, all pressures zero - shut in 30 min.

DST #2 4430-4450', op 1 hr, weak blow thruout  
rec. 180' gas in pipe, 40' slight gas cut  
mud w/few specks free oil, all pressures  
zero - shut in 30 mins.

DST #3 4450-4480', op 1 hr., weak to very  
weak blow thruout - flushed tool after  
30 min. Rec. 60' gas in pipe, 40' slight  
gas cut mud w/few specks oil, all pressures  
zero - shut in 30 mins.

DST #4 4480-4515', op 1 hr., rec. 15'  
drilling mud, all pressures zero - shut  
in 30 min.