

30-32-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- Warren Fee No. 4

SEC. 30 T. 32 R. 12W
SW NE NW
990' fr NL, 1098' fr EL, NW/4

Total Depth. 4538 PBD 4500
Comm. 6-19-55 Comp. 7-4-55
Shot or Treated. 500 gals. acid 4478-4496
Contractor. Chas. Hulme Drilling Co.
Issued. 9-3-55

County Barber
KANSAS



8 5/8 @ 318' w/ 200 sx cmt.
5 1/2 @ 4538' w/ 200 sx cmt.

Elevation. 1665 DF

Production. 98 BOPD

Figures indicate Bottom of Formations

surface soil, clay & shells	180
red bed, shale & shells	318
shale	660
shale, shells & salt	1515
shells	1775
lime	2350
shale & lime	2410
shale	2965
shale & lime	3070
lime	3190
lime & shale	3390
lime	3485
sand & shale	3783
shale	3929
lime	4434
lime & chert	4459
chert	4493
lime	4538
Total Depth	P.B. 4500

TOPS:

Heebner shale	3763
Toronto sand	3776
Lansing lime	3938
Base KC lime	4367
Marmaton lime	4377
Mississippi lime	4463

DST #1: 4448-93, open 1 hr. gas to
surf 22 min; too small to gauge, rec.
170' SO&GCM; IFP 15#, FFP 30#, BHP
800#/20 min.

Ran Schlumberger Survey

Producing formation Mississippi lime
4478-4496

Oil show 4478-4496