

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


35-32-12W

Company. BEARDMORE DRILG. & AURORA GAS CO.
Farm- Long No. 1

SEC. 35 T. 32 R. 12W
C NW NE

Total Depth. 4711'
Comm. 9-30-58 Comp. 10-21-58
Shot or Treated.
Contractor. Beardmore Drilg. Co.
Issued. 11-15-58

County Barber
KANSAS



Elevation. 1436' DF

CASING:
8 5/8" @ 215' cem. w/150 sx.

Production. Dry

Figures indicate Bottom of Formations.

cellar & soil	10
red bed	215
red bed	900
shale & shells	1460
shale & lime	1640
lime	1785
lime & shale	1915
lime	2050
lime & shale	3611
sand & shale	3716
lime	3740
lime & shale	3810
lime	4195
lime & shale	4250
lime	4309
chert & lime	4534
lime	4420
lime & chert	4455
lime	4520
lime & shale	4577
lime	4600
lime & shale	4670
shale	4677
sand	4685
sand & shale (?)	4690
sand	4711
Total Depth	RTD

TOPS:	
Elgin	3350
Heebner	3530
Lansing	3714
Mississippi	4304
Kinderhook	4431
Chattanooga	4558
Viola	4594
Simpson	4676

DST #4. 4680-4690 Shut in 30 min. open
2 hrs., shut in 30 min. Rec. 330' salt wtr.
IRHP 1800, FP 25, FBHP 1675. Hydrostatic 2635. Temp. 132.

DST #3. 4675-4685 Shut in 30 min. open
30 min. shut in 30 min. Rec. 7' mud.
IRHP 30, FP 10, FBHP 30, Hydrostatic
2620. No flow.

DST #2. 4309-4339 Shut in 30 min. open
1 hr., shut in 30 min., weak flow. Rec.
30' mud. IBHP 55, IF 23, FW 40, FBHP
55, Hydrostatic 2453. Temp. 107.

DST #1. 3566-3591 Straddle Test-Shut
in 30 min. Open 1 hr. Shut in 30 min.
Rec. 45' very slightly gas cut salt
wtr. IBHP 1200, FBHP 1080, FP 25,
Hydrostatic 2060. Temperature 135.