

3-32-13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HONAKER-DAVIS DRILLING COMPANY, et al
Farm- Gant No. 1

SEC. 3 T. 32 R. 13W
NW NW NW

Total Depth. 4735'
Comm. 12-5-57 Comp. 12-22-57
Shot or Treated.
Contractor. Honaker-Davis Drilling Company
Issued. 2-1-58

County Barber
KANSAS



CASING:

8 5/8" 281' cem w/175 sx

Elevation. 1646 RB.

Production. Dry

Figures indicate Bottom of Formations.

top soil & clay	40
red bed & shale	1700
lime & shale	3925
lime	3960
lime & shale	4070
lime	4440
lime & chert	4495
lime	4575
lime & chert	4630
lime	4652
lime & shale	4735RTD
Total Depth	

TOPS:	
Heabner	3643
Douglas Sand	3790
Lansing-Kansas City	3832
Base Kansas City	4244
Mississippian	4356
Kinderhook	4488
Viola	4578
Simpson Shale	4676
Simpson Sand	4704

#3 4343-4370, Tool open 20 min-30 min-
20 min, weak blow 15 min & 7 min, Rec.
12' mud, All O#.

#4 4706-4715, Tool open 20 min-60 min-
20 min, fair blow, Rec. 120' B & WCM*
120' HGC & SCCM, IBHP 1735#, FBHP 240#,
IFP 55#, FFP 75#.

*Halliburton ran a water analysis on
this water cut mud & reported forma-
tion water with very little filtrate
water.

HALLIBURTON DRILL STEM TESTS:

#1 3783-3797, Tool open 20min-60 min-
20 min., strong blow, Rec. 615' water,
IBHP 1488#, FBHP 1357#, IFP 48#, FFP
295#.

#2 4051-4070, Tool open 20 min-60 min-
20 min, strong blow, Rec. 1650' water,
IBHP 1630#, FBHP 1610#, IFP 515#,
FFP 950#.