

15-32-13W ✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- AYLWARD DRILLING CO.
Farm- Lenkner No. 1

SEC. 15 T. 32 R. 13W
C NW NW

Total Depth. 4515'
Comm. 3-14-63 Comp. 3-30-63
Shot or Treated,
Contractor.
Issued. 8-24-63

County Barber

KANSAS



Elevation. 1733' DF

Production. Dry

Figures Indicate Bottom of Formations.

redbed	190
red rock	208
red rock & shale	760
red rock	1010
shale	1230
shale & shells	1900
shale & lime	1955
lime & shale	2330
lime	2405
shale & lime	2550
lime & shale	2675
shale & lime strks.	2835
shale	3090
shale & lime	3370
lime & shale	3420
shale	3940
lime	4515
Total Depth	

TOPS: LOG

Elgin Zone	3606
Heebner	3767
Douglas	3806
Douglas Sandstone	3920
Lansing-Kansas City	3944
Base Kansas City	4359
Marmaton	4369
Massy Zone	4406
Mississippi	4450

DST #1 3896-3940' Op 70" Rec. 310'
muddy wtr. IBHP 1492#/30", FBHP 1425
#/30", IFP 156#, FFP 234#.

DST #2 4410-40' Op 70". Rec. 30'
mud. IBHP 67#/30", FBHP 22#/30" IFP
22#, FFP 22#.

DST #3 4449-69' Op 1 hr. 10". Rec.
65' mud. IBHP 67#/30", FBHP 89#/30",
IFP 44#, FFP 44#.