


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STRATA DRIG. & PETROLEUM DEV. CO.
Farm- Hopkins No. 1

SEC. 20 T. 32 R. 13W
SW SW SW

Total Depth. 4570'
Comm. 3-1-60 Comp. 3-15-60
Shot or Treated.
Contractor. Strata Drlg.
Issued. 12-3-60

County Barber
KANSAS



Elevation. Est. 1798' KB

CASING:
3 5/8" 219' cem w/175 sx.
4 1/2" 4570' cem w/75 sx.

Production. 23 BOPD

Figures indicate Bottom of Formations.

red bed	1422
shale & lime	2745
shale & lime streaks	2912
lime & shale	3960
shale	4033
lime	4570
Total Depth	

TOPS: SCOUT	
Heebner	3850
Brown Lime	4029
Lansing	4038
Marmaton	4445
Mississippi	4505

DST #1 4468-4498', op 45 mins., weak blow, rec. 15' mud, IFP 735#, FFP 0#, BHP 290#/20 mins.

DST #2 4498-4522', op 1 hr, gas to surf in 14 min., to small to meas. Rec. 190' fluid, 100' gas cut mud, 80' slightly oil cut mud, 10' oil cut mud. BHP 1615#/2 min still building.

DST #3 4522-4540', op 2 hrs., rec. 110' slightly oil cut mud. IFP 65#, FFP 80#, BHP 155#/20 min.