

25-32-13W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- FRED B. ANSCHUTZ
Farm- Lonker No. 1

SEC. 25 T. 32 R. 13W
NE NE NE

Total Depth. 4971'
Comm. 9-28-54
Shot or Treated.
Contractor.
Issued. 3-31-56

Comp. 10-25-54

County Barber
KANSAS



CASING:
8 5/8" 321' cem w/225 sx
5 1/2" 4556' cem w/100 sx

Elevation. 1655'

Production. 161 BO

Figures indicate Bottom of Formations.

surface clay	35
red bed & shale	145
sand	160
red bed	590
red bed & shale	1100
shale & shells	1550
shale & lime	1715
lime	2205
lime & shale	2325
lime & shale	2400
shale & lime	2730
lime & shale	2960
lime	3115
shale & lime	3210
lime	3430
lime & shale	3490
shale & lime	3756
lime	3836
shale & lime	3896
lime	4456
lime & chert	4542
lime & shale	4601
shale & lime	4609
lime & shale	4631
lime	4645
lime & shale	4747
lime	4844
lime & shale	4856
shale & sand	4875
sand & shale	4879
sand & lime	4903
sand & shale	4954
Arbuckle	4971 RTD
Total Depth	

Tops: Scout	
Elgin	3621
Heebner	3722
Douglas	3794
Lansing	3896
Mississippi	4457
Viola	4745
Arbuckle	4954