

28-32-13W


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- M. L. Hopkins No. 1

SEC. 28 T. 32 R. 13W
NW SW NE

Total Depth. 4493'
Comm. 9-9-65 Comp. 9-19-65
Shot or Treated.
Contractor. Strata Drlg, Inc.
Issued. 4-2-66

County Barber
KANSAS



CASING:
3 5/8" 361' cem w/215 sx.
5 1/2" 4492' cem w/150 s x.

Elevation. 1666' KB

Production. 8,600,000 CFG

Figures Indicate Bottom of Formations.

red bed & shale	355
lime	361
red bed & shale	1310
shale	1915
lime & shale	2040
lime	2250
lime & shale	3066
shale & lime	3250
lime & shale	3445
shale & lime	3715
lime, shale & sand	3892
lime	4010
chalky lime	4105
lime	4218
lime & chert	4280
lime	4370
lime & chert	4419
chert	4440
chert & lime	4474
lime & chert	4490
lime & chert (Log TD)	4493
Total Depth	

TOPS: LOG	
Heebner	3722
Toronto (Sample)	3733
Douglas	3759
Ireland	3788
Douglas Sand (Sample)	3866
Tonganoxie	3892
Lansing	3914
Base Kansas City	4324
Marmaton	4335
Mississippi	4424