

30-32-13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CRESCENT OIL & GAS
Farm- J. R. Hopkins No. 1

SEC. 30 T. 32 R. 13W
C NW NW

Total Depth. 4606'
Comm. 9-10-60 Comp. 9-24-60
Shot or Treated.
Contractor. Gabbert-Jones Drlg.
Issued. 3-25-61

County Barber
KANSAS



CASING:
13 3/8" 272' cem w/225 sx.
5 1/2" 4606' cem w/150 sx Pozmix & 15 sx Latex

Elevation. 1872' DF

Production. 8 BOPD

Figures Indicate Bottom of Formations.

red bed	1024
red bed & shale	1925
shale & lime	2135
lime	2525
lime & shale	2770
shale & lime	3220
lime	3470
shale & lime	3580
lime & shale	3755
lime	3995
lime & shale	4070
lime	4110
chalky lime	4175
lime	4606
Total Depth	

TOPS: ELECTRIC	
Heebner	3914
Douglas	3965
Lansing	4097
Base Kansas City	4512
Marmaton	4520
Massey	4562
Mississippi	4596

DST #1 4548-4581', op 50 min, flushed tool twice. Rec. 25' mud, ISIBHP 67#/30 min, IFP 33#, FFP 52#, FSIBHP 52#/30 min.

DST #2 4596-4603', op 2 hrs, gas to surf. but would not burn. Rec. 80' oil cut mud and 45' heavy, gassy oil. ISIBHP 1312#/30 min, IFP 18#, FFP 52#, FSIBHP 853#/30 min, still building.