

30-32-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- AYLWARD DRILLING CO.
Farm- Palmer No. 3

SEC. 30 T. 32 R. 13W
NE NW NE

Total Depth. 4590'
Comm. 6-21-60 Comp. 7-4-60
Shot or Treated.
Contractor. Aylward Drlg. Co.
Issued. 10-22-60

County Barber
KANSAS



Elevation. 1825' DF

Production. 146 BOPD

CASING:

8 5/8" 227' cem w/75 sx.
5 1/2" 4590' cem w/75 sx.

Figures Indicate Bottom of Formations.

gyp rock	55
red bed & shale	900
red rock	1170
shale & lime	1310
salt	1400
shale & shells	1700
shale & lime	1935
lime w/shale	2010
lime & shale	2120
lime	2450
lime & shale	2710
shale & shells	2950
shale & lime	3745
lime & shale	4070
lime	4523
Mississippi Chat	4590
Total Depth	

TOPS:

Heebner	3877
Brown Lime	4055
Lansing	4068
Marnaton	4470
Massey Zone	4502
Mississippi	4528

DST 4069-87', op 1 hr., weak blow Rec.
15' mud. IBHP 140#/20 mins., FBHP 130#/30 mins.
FP 0#-40#.

DST 4495-4520', op 1 hr., gas to surf./30
seconds, gauge 391 MCF/2 mins., 310 MCF/5 mins.
98 MCF/10 mins., ISTM/14 mins. Rec. 500'
HO&GCMW, 120' HO&GCM. IBHP 1340#/20 mins.
FBHP 1180#/30 mins., FP 200#-300#.

DST 4558-90', op 1 hr., weak blow. Rec.
900' SW. IBHP 1550#/20 mins., FBHP 800#/
30 mins., FP 105#-490#.

DST 4498-4553 (straddle) op 1 hr., str.
blow, gas to surf./2 mins., gauge 2,310
MCF, flowed oil in 45 mins., reversed out.
Rec. 120' gassy oil. IBHP 1600#/20 mins.
FBHP 1550#/30 mins. FP 410#-430#.