


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- Mattie Binning No. 1

SEC. 35 T. 32 R. 13W
Center SE/4 NW/4
660' fr EL, 660' from SL

Total Depth. 3986'
Comm. 7-24-54 Comp. 8-5-54
Shot or Treated.
Contractor.
Issued. 9-11-54

County Barber KANSAS



Elevation. 1637' DF

Production. Dry

CASING:

8 5/8" 473' cem w/275 sx

Figures Indicate Bottom of Formations.

rock, sand, and gravel	65
shale and shells	325
red bed and shells	473
shale	1520
anhydrite	1542
shale and lime	1670
lime	2275
lime and shale	2600
shale	3010
lime	3475
lime and sand	3570
sand	3645
lime	3658
shale	3715
shale and sand	3766
fine to medium grained light gray sub-angular micaceous sand	3790
light grey, fine to medium grained slightly limy micaceous sand	3870
sand, shale and lime	3899
light gray to tan, fine cry- stalline lime	3910
lime	3986
Total Depth	

Tops:

Elgin Sand	3563
Heebner Shale	3715
Douglas Sand 1st	3751
2nd Douglas Sand	3848
Brown Lime	3896
Lansing	3903

DRILL STEM TESTS: Halliburton

#1, packer set at 3765', used 25' anchor,
open 1 hr, very weak blow for 3 min., rec.
10' drilling mud, IFP 20#, FFP 36#, BHP 1151#.

#2, packer set at 3738', used 82' anchor,
open 1 hr., very weak blow to nothing in
1 min., rec. 8' of drilling mud, IFP 60#,
FFP 71#, BHP 262#.

Ran Schlumberger Survey