


35-32-13W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. BOWERS DRILLING CO. & NATL. COOP. REFG. SEC. 35 T. 32 R. 13W
Farm- Lonker No. 1 ASSN. C NE SE

Total Depth. 5015'
Comm. 7-21-62 Comp. 7-30-62
Shot or Treated.
Contractor. Bowers Drlg. Co.
Issued. 11-24-62

County Barber KANSAS



CASING:
8 5/8" 435' cem w/275 sx.
4 1/5" 4578'

Elevation. 1646' KB

Production. 19,550,000 CFGPD

Figures indicate Bottom of Formations.

clay	60
red bed	160
red bed & shale	875
shale & shells	1540
lime & shale	2050
lime	2180
shale & lime	2415
lime	2505
lime & shale	4130
lime	4415
lime & chert	4500
lime	4675
lime & shale	4726
shale	4790
lime	4914
Simpson	4964
shale lime	5000
Arbuckle	5015
Total Depth	

TOPS: LOG

Heebner	3761
Douglas	3847
Lansing-Kansas City	3913
Base Kansas City	4285
Mississippian Chert	4421
Mississippian Limestone	4480
Kinderhook Shale	4681
Viola	4782
Simpson Shale	4870
Simpson Sand	4883
Arbuckle	4985