

35 - 32 - 13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- **BOWERS DRILLING CO., INC.**
 Farm- **Lonker "A"** No. **1**

SEC. **35** T. **32** R. **13W**
 NE SW NE

Total Depth. **4660'**
 Comm. **11-4-62** Comp. **11-16-62**
 Shot or Treated.
 Contractor. **Aylward Drilling Company**
 Issued. **1-12-63**

County **Barber**
KANSAS



CASING:
8 5/8" 419' cem w/300 sx.

Elevation. **1655' KB**

Production. **DRY**

Figures Indicate Bottom of Formations.

sand	60
red bed	200
red bed & shale	370
sand	400
shale	744
shale & shells	1775
shale & lime	1932
lime & shale	2025
lime	2750
lime & shale	2940
shale w/some lime	3210
lime	3363
shale w/some lime	3491
shale & lime	3710
shale	3870
shale & lime	4020
lime	4255
lime & black shale	4320
lime	4351
lime & shale	4495
shale	4558
lime	4649
lime & chert	4658
lime	4660
Total Depth	

TOPS: LOG

Heebner	3718
Lansing	3898
Base Kansas City	4292
Conglomerate	4436
Reworked Mississippi Dolomite	4463
Mississippi Lime	4503

DST **4463-4495'** Op **1½ hr.** Shut in 30 min.
 Rec. 30' drilling mud. IBHP 120# - FBHP
 140#, FP 0-0#.

DST (Straddle) **4484-4505'** Op 1 hr.
 Rec. 10' mud. All pressures 0.