

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock,
Wichita, Kansas


35-32-13W

Company- BOWERS DRILLING
Farm- Weidner No. 1

SEC. 35 T. 32 R. 13W
C WL SW

County Barber
KANSAS

Total Depth. 4524
Comm. 7-10-64 Comp. 7-23-64
Shot or Treated.
Contractor. Bowers Drlg.
Issued. 12-5-64



CASING:

Elevation. 1675' KB

8 5/8" 313' cem w/ 225 sx
5 1/2" 4524' cem w/ 150 sx

Production. 4,400,000 CFG

Figures Indicate Bottom of Formations.

red bed	500
red bed, shells & shale	1373
shale & shells	1965
lime & shale	2288
lime	2480
lime & shale	3585
sand & shale	3870
sand, shale & lime	4009
lime	4071
chalky lime & shale	4177
lime	4205
lime-shale	4374
lime	4470
shale-lime chert	4481
lime	4524
Total Depth	

TOPS: LOG	
Elgin zone	3544
Elgin sand	3568
Heebner	3746
1st Douglas sand	3852
2nd Douglas sand	3898
Lansing	3920
Base Kansas City	4312
Massey	4424
Mississippi	4452