

36-32-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BOWERS DRILLING CO., INC.  
Farm- Lonker "B" No. 1

SEC. 36 T. 32 R. 13W  
C SW

Total Depth. 4579'  
Comm. 11-20-62 Comp. 12-3-62  
Shot or Treated.  
Contractor. Aylward Drilling Co.  
Issued. 2-16-63

County Barber  
KANSAS



CASING:  
8 5/8" 424' cem w/325 sx.  
4 1/2" 4577' cem w/100 sx.

Elevation. 1675' KB

Production. 25,005,000 CFG &  
Est. 250 BOPD

Figures Indicate Bottom of Formations.

|                   |      |
|-------------------|------|
| red bed & shale   | 106  |
| red bed & clay    | 710  |
| shale & shells    | 1710 |
| shale             | 1900 |
| shale & shells    | 2075 |
| lime              | 2185 |
| lime & shale      | 2325 |
| lime w/some shale | 2500 |
| lime              | 2670 |
| lime & shale      | 3075 |
| lime              | 3388 |
| lime & shale      | 3525 |
| shale & lime      | 3950 |
| lime              | 4445 |
| lime & chert      | 4480 |
| chert & chat      | 4492 |
| chert             | 4500 |
| cherty lime       | 4518 |
| lime              | 4579 |
| Total Depth       |      |

TOPS: LOG

|                     |      |
|---------------------|------|
| Heebner             | 3778 |
| Douglas Sand        | 3880 |
| Lansing-Kansas City | 3948 |
| Base Kansas City    | 4318 |
| Mississippi Chert   | 4452 |
| Mississippi Lime    | 4511 |

DST 4450-4472' Op 1 hr. SI 30" GTS/2",  
Gauge 686,000 CF/5", 1,020,000/10" stabilized.  
IBHP 1628# - FBHP 1541#, FP 161#-149#.

DST 4472-4492' Op 2 hr. SI 30"GTS/3"  
Gauge 887,000/3", 1,020,000/5", 670,000/  
15", 214,000/30", ISTM/85". Rec. 808'  
fluid: Gsy oil & 312' mdy gsy oil. IBHP  
1599# - FBHP 1428#, FP 150#-127#.

DST 4493-4518' Op 1½ hr. SI 30". Rec. 30'  
SI.OCM. IBHP 25# - FBHP 49#, FP 0#-0#.