

Open: Petroleum Technologies
6-325-13W
SW SE NE

CONFIDENTIAL

Released

MAR 8 1985
6-32-13W

WICHITA BRANCH

BROOK #6-1 DRILL STEM TESTS

Computer Inventoried

DST #1 3956-3966/ 30-60-45-90
IHP 1892# IFP 30-119# ISIP 1420#
FFP 129-238# FSIP 1420# FHP 1852#
Recovered 480' salt water

DST #2 4029-4042/ 30-40-45-90
1st Open GTS/4" Inc. to 235 MCFPD
2nd Open Gauge Inc. to 275 MCFPD and Stab.
IHP 2000# IFP 129-188# ISIP 1439#
FFP 79-139# FSIP 1380# FHP 1912#
Recovered 220' heavy oil cut mud

DST #3 4205-4211/ 30-60-45-90
IHP 2059# IFP 50-248# ISIP 1498#
FFP 285-374# FSIP 1508# FHP 2039#
Recovered 640' Salt Water

DST #4 4281-4294/ 30-60-45-90
Tool slid 12' on 1st opening
1st Open GTS/28" TSTM
2nd Open GTS/1" 94MCFPD, Decrease to 33 MCFPD and Stab.
IHP 2099# IFP 308-208# ISIP 1587#
FFP 139-186# FSIP 1587# FHP 2059#
Recovered 420' gas cut mud and 90' gas cut salt water

DST #5 4304-4319/ 30-60-45-90
1st Open GTS/10" Inc. to 65 MCFPD
2nd Open Inc. throughout to 98 MCFPD
IHP 2118# IFP 79-159# ISIP 1626#
FFP 109-288# FSIP 1616# FHP 2030#
Recovered 120' heavy oil cut gassy mud, 180' gas cut oil
and 300' salt water.

DST#6 4388-4440/ 30-60-45-90
1st Open GTS/9" inc. to 32 MCFPD
2nd Open Decrease from 41 to 23 MCFPD and Stab.
IHP 2158# IFP 149-288# ISIP 1626#
FFP 208-447# FSIP 1626# FHP 2079
Recovered 540' heavy oil and gas cut salt water and 600' salt water

MAY 30 1985
KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1985

CONSERVATION DIVISION
Wichita, Kansas

CONFIDENTIAL

541782

MAR 8 1985

State Geological Survey
WICHITA BRANCH

DST #7 4471-4478; 30-60-45-90

1st Open Strong Blow no GTS

2nd Open GTS/4" Inc. to 7 MCF

IHP 2216#

IFP 20-30#

ISIP 1675#

FFP 20-30#

FSIP 1675#

FHP 2158#

Recovered 60' of slight oil cut mud (3% Oil) and 30' of oil cut (6% oil)

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1985

CONSERVATION DIVISION
Wichita, Kansas

MAY 30 1985

STATE GEOLOGICAL SURVEY
WICHITA BRANCH