


State Kansas Field WTC 5
 Company TEXAS Co. County Meade
 Farm A. D. SANDERS No. #1
 Sec. 13 Twp. 32 Range 29W

Spot SE NW NE

Contractor Noble

Remarks



Comm. 9/14/56 Comp. 10-31-56

Elev. DF 2632 GL 2632 KB TD 5944 PB

Pay 5588-90
5568-72

I.P. 9,153 MCF Press. SIP 1620

Casing Record: 13 3/8 7" 5830/250

20" 10 3/4 1480/1100 5 1/2"

16" 8 5/8

	Sample	Log
SEP 5	Heel 2653	Heel 4363
holding to check	WINF 2722	Top 4406
Report + plot	UFR 2805	Lums 4528
reported incorrect loc. holding for further information	UFR 2846	Marm 5148
location	Florence 2912	Cher 5267
SEP 12	WTC 2978	Atoka 5365
SEP 19 ϕ 2425	Top 3942	MOR 5510
SEP 26 0.5T 2861-81 op	Heel 4364	Miss 5518
1 hr. MC 100' MC SW FP	Top 4407	5' ben 5807
0-60 BHP 660/20	Jana 4546	
ϕ 3880	Marm 5146	
OCT 3 ϕ 5168	Pik 5324	
OCT 10 ϕ 5540-99 MC 58'	Atoka 5446	
12' 5h. dk grey lbl.	MOR 5510	
5' 5h AS ABOVE low streaks	Miss 5562	
5' 5h + low.		
8' low. lt grey to buff sand.		
5' thin olive & flav.		
28' fr to sandy clay. from low. oil in partings		
scat stain + odor to 5581- (5588-91 5593-98) "tite"		
0.5T 5567-5611 op 2 hrs. full to T.D. 975.55" g		
29 MCF in 1 hr g 32 MCF in 1 1/2 hrs		
36 MCF in 2 hrs. low 60' gcm. FP 90 BH 1690/30		

~~9-5611 ahead.~~

OCT 17 p 5611-36 rec 25'

1' low. lt gr to buff kln slip ov.

6' sh. dk gr to green - v. calc.

1 1/2' low. buff fr to v. gr. kln slip fore

1/2' low. gr to buff.

13' sh. gr to green calc. fore streaks of den low.

3' low. gr to buff fr to v. gr to den shi kln.

RTD 5944 TAN 7" to 5830/250

WOC

OCT 24 CG 5600 PF 29/5584-90 16/5568-72

A/500 M, 92,445 MCF PF 32/5550-58

91,885 MCF A/3000 3hr BD 3,208 MCF

SI 14 hrs 20' OF 8,519 MCF SITP 1590

W.O.T.

OCT 31

72/20 9 9,153 MCF SIP 1620.

Prod from Chester

AMARILLO TOPS

2642 KB

Winfield 2723 (-81) XW

Heebner 4386 (-1744)

Douglas 4397 (-1755)

Lansing 4526 (-1884)

Marmaton 5109 (-2467)

Morrow 5536 (-2894)

Chester 5548 (-2906) 9,153 MCF

St. Gen 5818 (-3176)

TD 5944 (-3302)