

19-32-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- CRESCENT OIL & GAS CORP.  
Farm- H. Mills No. 1

SEC. 19 T. 32 R. 13W  
C SW SW

Total Depth. 5047'  
Comm. 12-14-60 Comp. 1-5-61  
Shot or Treated.  
Contractor. Gabbert-Jones Drlg. Co.  
Issued. 4-1-61

County Barber  
KANSAS



Elevation. 1858' RB/

Production. 5,000,000 CFG

CASING:

13 3/8" 269' cem w/250 sx.  
5 1/2" 4679' cem w/100 sx.

Figures Indicate Bottom of Formations.

red bed & shells	269
red bed & shells	1026
red rock & shells	1440
shale & shells	1900
lime	1990
lime & shale	2165
lime	2745
lime & shale	3360
lime	3525
lime & shale	4073
lime	4577
chert & lime	4627
lime	4795
shale	4855
Viola	4878
lime	4945
cherty lime	4967
lime & shale	5020
sand & shale	5038
Simpson	5047
Total Depth	

TOPS: SCOUT

Heebner	3893
Lansing	4042
Marmaton	4491
Mississippi	4560
Kinderhook	4797
Simpson Shale	4984
Simpson Sand	5010