

19-32-13W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- SINCLAIR OIL & GAS CO.
 Farm- Palmer No. 1

SEC. 19 T. 32 R. 13W
 SE SE SE

Total Depth. 5102'

Comm. 1-9-59

Comp. 2-8-59


County Barber

KANSAS

Shot or Treated.

Contractor. Garvey Drilg. Co.

Issued. 4-25-59



CASING:

13 3/8" 290' cem w/300 sx.

5 1/2" 4734' cem w/125 sx.

Elevation. 1830' DF

Production. 130 BOPD &
 730,000 CFG

Figures indicate Bottom of Formations.

surface soil & red bed	325
red bed	1057
lime, shells & shale	1250
shale & gyp	1345
shale	1640
lime	2020
lime & shale	2057
lime	2250
shale & lime	2588
lime	2796
shale	2920
lime & shale	3237
lime	3355
lime & shale	3497
lime	3581
lime & shale	3958
lime, shale & sand	4101
lime	4195
lime & sand	4313
lime	4523
chert	4558
chert & shale	4582
lime & chert	4595
lime	4950
sand	4954
sand & lime	4975
lime & shale	4993
lime & sand	5008
shale & sand	5010
lime & shale	5086
lime	5102
Total Depth	

TOPS: SCOUT

Heebner	3867
Douglas Shale	3910
Lansing	4058
Marmaton	4460

Mississippi	4524
Kinderhook	4780
Viola	4854
Simpson Shale	4976
Simpson Sand	5011
Arbuckle	5084