

13-32-14W ✓


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- OLSON OIL COMPANY
Farm- DeGeer "A" No. 2

SEC. 13 T. 32 R. 14W
C SE SW

Total Depth. 4800'
Comm. 10-14-62 Comp. 11-4-62
Shot or Treated.
Contractor. Patton Drilling Co.
Issued. 3-2-63

County Barber
KANSAS



Elevation. 1780' KB

Production. 9000 MCFG & 40 BOPD

CASING:

10 3/4" 269' cem w/175 sx.
8 5/8" 906' cem w/100 sx.
5 1/2" 4563' cem w/150 sx.

Figures Indicate Bottom of Formations.

red bed 274
red bed & shale 385
shale & shells 740
shale, Anhydrite & shells 860
shale & shells 1820
lime & shale 1963
lime 2500
lime & shale 3863
sandy lime & shale 3944
shale & lime 3982
lime 4306
lime & shale 4487
lime cherty 4540
lime 4665
lime & shale 4709
lime 4800
Total Depth

TOPS: SAMPLE

Heebner 3806
Toronto 3818
Douglas 3850
Lansing-Kansas City 3983
Base Kansas City 4388
Marmaton Zone 4397
Massey 4442
Mississippi 4470
Kinderhook 4706
Maquoketa 4722

Meas. from RB, 8' RB to Ground Level.